



PLANTING SCHEDULE - 138 ALLEN STREET, BUFFALO

| KEY | QTY | BOTANICAL NAME | COMMON NAME | MIN. SIZE | REMARKS |
|-------|-----|----------------------------------|----------------------|------------------------|------------------|
| GB-2 | 2 | DECIDUOUS TREES | | | |
| GB-1 | 2 | SHRUBS | WINDHAM TREE | 2" CAL. | BBB |
| PF-6 | 6 | POTENTILLA FRUTICOSA 'GOLDINGER' | GOLDINGER POTENTILLA | NO. 5 CONT. / 4-2" HI. | SPRKE 3"-4" O.C. |
| EX-10 | 10 | BRUS 'GREEN KALEST' | GREEN VEGET BOWWOOD | 24" HI. MIN. | BBB |

Luminaire Schedule

| Symbol | Qty | Label | ILP | Description |
|--------|-----|-------|-------|-------------------|
| □ | 1 | A | 1,000 | TLED-NFL-79-VS-5K |

WALL MOUNTED LIGHT FIXTURE IS EXISTING

- GENERAL NOTES:**
- INSTALL ALL MATERIALS TO MANUFACTURERS' RECOMMENDATIONS AND BEST STANDARDS OF TRADE INVOLVED.
 - SUBSTITUTIONS SHALL BE MADE ONLY WITH OWNERS APPROVAL AND BE OF EQUIVALENT QUALITY TO WHAT IS SPECIFIED.
 - WORK SHALL BE COMPLETED IN STRICT ACCORDANCE WITH ALL LOCAL CODES AND OSHA SAFETY RULES AND REGULATIONS.
 - VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE BEGINNING WORK. DISCREPANCIES IN CONDITIONS SHOWN ON DRAWINGS PRIOR TO PROCEEDING WITH THE WORK.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ANY EXISTING STRUCTURES TO REMAIN AND ANY FINISH MATERIAL INSTALLED WHILE WORKING ON OTHER COMPONENTS.
 - CONTRACTOR SHALL KEEP JOB FREE OF DEBRIS AND MAKE FINAL CLEANUP TO SATISFACTION OF OWNER.
 - CONTRACTOR SHALL ASCERTAIN THE LOCATION OF ALL UTILITIES BEFORE BEGINNING WORK AND/OR INSTALLATIONS. COORDINATE ALL WORK WITH THE APPLICABLE UTILITY COMPANIES.

- PROPOSED UTILITY LEGEND**
- PROPOSED STORM SEWER: — ST —
 - PROPOSED SANITARY SEWER: — 6" SA —
 - PROPOSED WATERLINE: — 1" W —
 - PROPOSED CATCH BASIN: ■ CB
 - PROPOSED YARD DRAIN: ● YD
 - PROPOSED MANHOLE: ● MH
 - PROPOSED HYDRANT ASSEMBLY: ●
 - PROPOSED GATE VALVE: ⊕ GV
- NOTE:** FOR PROPOSED VALVE BOXES, CLEANOUTS, ETC. INSTALL A 3,000 PSI CONCRETE COLLAR AROUND THE ITEM AT GRADE. THE COLLAR SHALL BE A MINIMUM OF 6" WIDER ON ALL SIDES THAN THE BOX, CLEANOUT, ETC. THE COLLAR SHALL BE A MINIMUM OF 6" THICK.

NOTE: ALL EXISTING WATER MAIN / TAP LOCATIONS / HYDRANT INFORMATION HAS BEEN PROVIDED BY CITY OF BUFFALO WATER DEPARTMENT. APPROXIMATE CONTRACTOR TO COORDINATE & VERIFY WITH COBW PRIOR TO CONNECTION.

WATER SERVICE TO HAVE 5'-0" MIN. COVER